

**BEST POWER**

Power	55%	65%	75%
FF Gal/h	7,8	8,8	10,0
FF Liter/h	29,5	33,3	37,9
FF Kg/h	21,2	24,0	27,2

**WEIGHTS**

Basic Empty Weight	Kg	665
Arm Aft Datum(empty w)	m	2,193
MTOW	Kg	1055
MLW	Kg	1055
Max baggage	Kg	91
Tillsatsvikt	Kg	390

**TRUE AIRSPEED Best Power**

PA	ISA	True Airspeed KTS		
		55%	65%	75%
10	13	96	106	115
20	11	97	107	116
30	9	98	108	117
40	7	99	109	118
50	5	100	110	120
60	3	101	111	122
70	1	102	112	124
80	-1	103	113	125
90	-3	104	114	127
100	-5	105	115	125

ISA + 10 gives +1 KTS

ISA - 10 gives -1 KTS

Saknas hjulkåpor minskar farten med 7 knop

**SPEED**

		KIAS	
X-W	Max Demo Crosswind	KTS	17
Vs	Stall Speed Flaps 40		44
Vs	Stall Clean		50
Vx	Best Angel of Climb Speed		63
Vy	Best Rate of Climb Speed		79
	En Route Climb Speed		87
Vg	Power Off Glide Speed		73
Vfe	Max Flaps Speed		103
Va	Design Maneuvering	1055 Kg	111
	Speed	695 Kg	88
Vno	Max Structural Cruising Speed		126
<b>Vne</b>	<b>Red Line</b> Never Exceed Speed		160
	Initial Approach Speed		70
	Final Approach Speed 40		63

**FUEL ADD**

	Holding	Taxi
Power %	55%	
Min	45	
Gal	5,9	1,1
Liter	22,1	4,2
Kg	15,9	3,0
<b>Route Reserve 10 %</b>		

**FIELD REQUIREMENTS**

MTOW - IAS - SL - HARD RW - NO WIND				
	Speed KIAS	Flaps	Roll m	50 ft m
<b>Take off</b>				
Normal	50	0	305	533
Short Field	50	25	305	457
<b>Landing</b>				
Normal	63	40	180	338

FUEL	Total	Usable Fuel	
		Full	Standard
Gal	50	48	34
Liter	189	182	128
Kg	136	129	91

**FLIGHT PLAN**

TYPE	P28A		
WAKE TURBULENCE CAT	L		
EQUIPMENT	SDGRY/C	PBN/B2S1	
EMERGENCY RADIO	ELT		

OIL	Max	Min
US quarts	8	2

**POWER SETTING**

	Full Power
Climb	Chart
Cruise	Chart
Holding	2300
Descend	1900
ILS Appr	1900
NDB Appr	1700


**ÄGARE**

FK Hässlö Air
Lars-Göran Johansson
Aspgatan 39, Kumla
Telefon 070-228 70 85

# WEIGHT AND BALANCE

SE-IDY

Item	Weight Kg	Arm m	Moment
Basic Empty Weight	665	2,193	1 458
Pilot and Front Passenger		2,045	
Passenger Rear Seat		3,000	
Fuel: Full 182 L=129 Kg, Standard 128 L=91 Kg		2,413	
Baggage Max 91 Kg		3,627	
Total Loaded Airplane MAX 1055 Kg			



W/V	Alt FL	TAS	TT	wca	TH	var	MH	BRYTPUNKT	DISTANS		GS	TID		BRÄNSLE	
								S	INT	ACC		INT	ACC	INT	ACC
								1							
								2							
								3							
								4							
								5							
								6							
								7							
								8							
								9							
								10							
Väder och NOTAM								Block In		Landning		Sträcka		Sträcka	
								Block Ut		Start		Reserv		Reserv	
												Summa		Summa	
												Altern		Altern	
Datum			Befälhavare					Blocktid		Flygtid		Extra		Extra	
												Total		Total	